Sample Gutter Co.

(760) 555-0142 · office@samplegutterco.example
samplegutterco.example
CA Lic #0000000 · Insured

ESTIMATE

EST-20261104-001
Date 11/4/2026
Valid through 12/4/2026

PREPARED FOR

735 Mission Grove Place, Escondido, CA

735, Mission Grove Place, Mission Park, Escondido

SERVICE

Rain gutter cleaning

5 buildings · about 1,821 ft of gutter · 18 downspouts

Thank you for asking Sample Gutter Co. to look at your gutters. We estimated the gutter length of each building from its mapped outline, so we can give you a preliminary range before anyone comes out. The final price is confirmed on site.

PRELIMINARY ESTIMATE

$3,675 – $7,200

Estimated from mapped building outlines, not an on-site visit. Final price confirmed on site; it may be higher or lower.

WHERE A FINAL PRICE TENDS TO LAND

$3,675
Lighter buildup, clear downspouts, easy access

$7,200
Heavy buildup, clogged downspouts, harder access

What we check on site: how much is in the gutters, whether the downspouts drain, roof access and pitch, and the condition of the gutters themselves. This estimate assumes moderate buildup and normal access. A volume discount is included for the footage above 1,000 ft.

WHAT WE ESTIMATED

Building	Stories	Gutter (ft, est.)	Downspouts
Bldg 1 (6,684 sq ft)	3	352	4
Bldg 2 (6,003 sq ft)	3	418	4
Bldg 3 (7,217 sq ft)	3	362	4
Bldg 4 (6,587 sq ft)	3	348	3
Bldg 5 (6,588 sq ft)	3	341	3
Total		**1,821**	**18**

HOW THE RANGE ADDS UP

3-story gutters: 1,821 ft × $1.75–3.50	$3,187–$6,374
Adjustment for moderate debris	× 1.15
Volume discount on footage above 1,000 ft (10% of the charge for 821 ft)	-$165–$330
18 downspouts × $10	$180
Preliminary estimate	**$3,675 – $7,200**

WHAT IS INCLUDED

Removal of all leaves and debris from gutters, flushing of downspouts to confirm flow, bagging and haul-away of debris, and cleanup of the work area.

ASSUMPTIONS

Gutter footage is estimated from mapped building outlines, not a tape measure. Story counts, downspout counts, debris level and access are assumptions until a technician is on site.

THE FINE PRINT

This is a preliminary estimate based on roofline footage estimated from building outlines and on assumed conditions. It is not a quote or a contract. The final price is confirmed on site after an inspection and may be higher or lower than this range.

NEXT STEP

Call or text (760) 555-0142 or email office@samplegutterco.example to set up an on-site visit. We confirm the final price in writing after the visit, and nothing is scheduled until you approve it.

Prepared by Jorge, Sample Gutter Co. Gutter footage is estimated from mapped building outlines or manual measurements. Actual gutter runs and site conditions require confirmation.